

Date: Tuesday, 12/6/2005 9:56:16 AM
 User: Linda Lacelle

Process Sheet

SPLIT - 2

Customer : CU-DAR001 Dart Helicopters Services	Drawing Name : GHW MOD KIT
Job Number : 25128	
Estimate Number : 11182	
P.O. Number : N/A	Part Number : D350615041
This Issue : 12/6/2005 S.O. No. : N/A	Drawing Number : D2282 REV E
Prsht Rev. : NC	Project Number : N/A
First Issue : N/A Type : SMALL / MED FAB	Drawing Revision : E
Previous Run : 25127	Material : N/A
Written By : SEE COMMENT BELOW	Due Date : 1/18/2006 Qty: 32 Um: 100 Each
Checked & Approved By : SEE COMMENT BELOW	
Comment : Est Rev:K Removed Manufacturing 05-12-05 JLM	

Additional Product

Job Number:



Seq. #: Machine Or Operation: Description :

1.0

DC

DOCUMENT CONTROL



Comment: DOCUMENT CONTROL

Photocopy bluefile and type labels as per PPP D350-615-041CHG003

2.0

25128A

"T" HANDLE ASSEMBLY



Comment: Sub-Component "T" HANDLE ASSEMBLY

3.0

25128B

SADDLE ASSEMBLY



Comment: Sub-Component SADDLE ASSEMBLY

4.0

D30153

Lock Nut



Comment: Qty.: 3.0000 Each(s)/Unit Total : 300.0000 Each(s)

Pick:

Qty Part Number Description Batch

3 D3015-3

5/16 Locknut

~~B2514C~~ B25149

5.0

D30155

SS Nylock Nut 7/16



Comment: Qty.: 1.0000 Each(s)/Unit Total : 100.0000 Each(s)

Pick:

Qty Part Number Description Batch

1 D3015-5

7/16 Locknut

B21824C

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: GHW MOD KIT

Job Number: 25128

Part Number: D350615041

Job Number:



Seq. #:	Machine Or Operation:	Description :
---------	-----------------------	---------------

6.0	51618015C	SS Bolt 5/16-18 1.5" L
-----	-----------	------------------------



Comment: Qty.: 3.0000 Each(s)/Unit Total: 300.0000 Each(s)

Pick:

Qty Part Number Description Batch

3 5/16-18-015C 5/16 Bolt 1.5 Long M18714 X243, M16999 X 21

7.0	516WC	SS Flat Washer 5/16
-----	-------	---------------------



Comment: Qty.: 12.0000 Each(s)/Unit Total: 1200.0000 Each(s)

Pick:

Qty Part Number Description Batch

12 5/16WC 5/16 Flat Washer M18714 X 446, M19611 X 732

8.0	71614050C	SS Bolt 7/16 5" Long
-----	-----------	----------------------



Comment: Qty.: 1.0000 Each(s)/Unit Total: 100.0000 Each(s)

Pick:

Qty Part Number Description Batch

1 7/16-14-050C 7/16 Bolt 5.0 Long M18714 X 71, M19490 X 27

9.0	716WC	SS Flat Washer 7/16
-----	-------	---------------------



Comment: Qty.: 2.0000 Each(s)/Unit Total: 200.0000 Each(s)

Pick:

Qty Part Number Description Batch

2 7/16wc 7/16 Washer M18714

1 D2282-041(Ref) "T" Handdle Assembly B25128A

1 D2282-043 (Ref) Saddle Assembly B25128B

10.0	SMALL FAB 1	SMALL & MEDIUM FAB RESOURCE 1
------	-------------	-------------------------------



Comment: SMALL & MEDIUM FAB RESOURCE 1

Assemble D2282-041 with D2282-043 as per Dwg D350-615 Only engage one thread on three 5/16-18-015C bolts

DL 06-01-26 (61)

11.0	QC5	INSPECT WORK TO CURRENT STEP
------	-----	------------------------------



Comment: INSPECT WORK TO CURRENT STEP

h 06-01-26

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: GHW MOD KIT

Job Number: 25128

Part Number: D350615041

Job Number:



Seq. #:

Machine Or Operation:

Description :

12.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

Identify and pack for shipping as per PPP D350-615-041

Location: _____

PPP Rev: E

6/1/24



69

13.0

DC

DOCUMENT CONTROL



Comment: DOCUMENT CONTROL

Inspection Level 21

545 06/01/30

DP 06/01/30




Job Completion




DART**RELEASED**

05/09/16

DESIGN BW	DRAWN BY <i>[Signature]</i>	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED <i>[Signature]</i>	APPROVED <i>[Signature]</i>	DRAWING NO. D2282	REV. E SHEET 1 OF 2
DATE 05.06.07		TITLE HANDLE TUBES	SCALE 1:1
A	94.10.14	NEW ISSUE	
B	95.03.23	RE-DESIGN	
C	97.10.20	CORRECTED NUMBERING SCHEME	
D	05.03.16	REDESIGN D2282-5; 0.795 WAS 0.750	
E	05.06.07	D2282-5 304 SS WAS 303 SS; R0.063 x 0.063 WAS R0.080 x 0.030	

**D2282-3****D2282-7****D2282-3/-7 TUBE:**

- 1) MATERIAL: T304/T316 3/8 SCHEDULE 40 (REF. DART SPEC. M304TR0.675W.091)
- 2) BREAK ALL UNMARKED SHARP EDGES 0.005 TO 0.010
- 3) ALL DIMENSIONS ARE IN INCHES
- 4) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED

**D2282-5****D2282-5 STEM:**

- 1) MATERIAL: AISI 304 STAINLESS STEEL (REF. DART SPEC. M304R0.750)
- 2) BREAK ALL UNMARKED SHARP EDGES 0.005 TO 0.010
- 3) ALL DIMENSIONS ARE IN INCHES
- 4) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED

Copyright © 1994 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

